



ADA TITLE II ASSESSMENT



Prepared for:

Montgomery County Public Schools
45 West Gude Drive, Suite 4100
Rockville, Maryland 20850

ADA TITLE II ASSESSMENT

Paint Branch High School
14121 Old Columbia Pike Road
Burtonsville, Maryland 20866

PREPARED BY:

EMG
10461 Mill Run Circle, Suite 1100
Owings Mills, Maryland 21117
800.733.0660
www.EMGcorp.com

EMG CONTACT:

Michael Nelson
Program Manager
800.733.0660 x6244
mnelson@emgcorp.com

EMG Project Number:

123821.17R000-180.303

Date of Report:

October 29, 2019

On Site Date:

October 15-18, 2018



1 Accessibility

Generally, Title II of the Americans with Disabilities Act (ADA) prohibits discrimination by entities to access and use of the government entity’s programs, services, and facilities on the basis of disability. Regardless of their age, these areas and facilities must be maintained and operated to comply with the Americans with Disabilities Act Accessibility Guidelines (ADAAG), and applicable state and local accessibility regulations.

Buildings completed and occupied after January 26, 1992 are required to comply fully with ADAAG. Existing facilities constructed prior to this date are held to the lesser standard of complying to the extent allowed by structural feasibility and the financial resources available, or a reasonable accommodation must be made. The ADA guidelines were clarified and amended in 2010 based on a clarification by the Department of Justice known as the “2011 Site Construction Tolerances Addendum to the 2010 ADA Standards for Accessible Design.” The aforementioned document defines the acceptable and allowed construction tolerances above or below the requirements established in the 2010 ADA Standards for barriers related to:

- Accessible Parking
- Pedestrian Path of Travel
- Building Entrances
- Interior Spaces

The scope of the ADA Assessment, as defined in the scope of work, is limited to exterior and interior areas covered by the ADA.

Based on the onsite review, EMG found that barriers to accessibility exist at Paint Branch High School. The observed elements were analyzed using the 2010 ADA Standards for Accessible Design and state accessibility codes.

1.1 Accessibility Summary Table

Based on the onsite review, EMG found that barriers to accessibility exist at Paint Branch High School. The observed elements were analyzed using the 2010 ADA Standards for Accessible Design and state accessibility codes.

EMG’s assessment of the subject property identified the following areas of concern:

| Facility / Building | Priority 1 Items | Priority 2 Items | Priority 3 Items | Priority 4 Items | Priority 5 Items | Total Items |
|--------------------------|------------------|------------------|------------------|------------------|------------------|-------------|
| Paint Branch High School | 52 | 32 | 44 | 4 | 19 | 155 |
| Grand Total | 52 | 32 | 44 | 4 | 19 | 155 |

1.2 Barrier Summary Table

The following table summarizes the barriers that were identified. The costs provided are order of magnitude estimates. Costs will vary depending upon the location and volume of work performed. Individual observation details may be found in Appendix A.



| Id | Facility | Building | Assembly | Type | Barrier Priority | Detail | Location Description | ADA |
|--------|--------------------------|----------------|-----------------------|---------------------------|------------------|--|---|-----|
| 142464 | Paint Branch High School | Athletic Field | Compliant Amenity | Compliant Amenity | 0 | The entire amenity is compliant. | Baseball Field Press Box/Storage Room | ADA |
| 142453 | Paint Branch High School | Athletic Field | Amenity Not Evaluated | Amenity Not Evaluated | 0 | The amenity is under construction and cannot be evaluated. | Softball field bleachers | ADA |
| 142482 | Paint Branch High School | Exterior | Amenity Not Evaluated | Amenity Not Evaluated | 0 | The amenity is not part of the required accessible route from the public right- of- way. | Ramp along west road | ADA |
| 142405 | Paint Branch High School | Interior | Amenity Not Evaluated | Amenity Not Evaluated | 0 | The amenity is not regulated by the ADA. | Main Stair | ADA |
| 142457 | Paint Branch High School | Athletic Field | Exterior Access Route | Stairs | 1 | Steps do not have uniform and compliant riser heights. | Football field - visitor bleachers | ADA |
| 142458 | Paint Branch High School | Athletic Field | Exterior Access Route | Ramp | 1 | The ramp running slope exceeds 1:12 (8.33%). | Football field - visitors bleachers | ADA |
| 142459 | Paint Branch High School | Athletic Field | Exterior Access Route | Exterior Accessible Route | 1 | The accessible route has running slopes greater than 1:20 (5%). | Football field - visitors bleachers | ADA |
| 142466 | Paint Branch High School | Athletic Field | Exterior Access Route | Ramp | 1 | A ramp is required but not provided. | Baseball field dugouts | ADA |
| 142467 | Paint Branch High School | Athletic Field | Exterior Access Route | Ramp | 1 | The ramp has a rise greater than 6"; however, handrails are not provided. | Baseball field dugouts | ADA |
| 142468 | Paint Branch High School | Athletic Field | Exterior Access Route | Stairs | 1 | Handrails are not provided. | Baseball field dugouts | ADA |
| 142469 | Paint Branch High School | Athletic Field | Exterior Access Route | Protruding Object | 1 | Protruding objects in the 27" to 80" range above finished floor protrude more than 4" into the circulation path along the interior accessible route. | Baseball field dugouts | ADA |
| 142471 | Paint Branch High School | Athletic Field | Exterior Access Route | Gate | 1 | The gate is less than 32" in width. | Exterior basketball court | ADA |
| 142448 | Paint Branch High School | Athletic Field | Exterior Access Route | Ground Surface | 1 | Ground surfaces are not firm, stable and slip resistant. | Softball field team benches | ADA |
| 142452 | Paint Branch High School | Athletic Field | Exterior Access Route | Gate | 1 | The gate does not have the required maneuvering clearance area. | Softball field bleachers | ADA |
| 142455 | Paint Branch High School | Athletic Field | Exterior Access Route | Ramp | 1 | The ramp running slope exceeds 1:12 (8.33%). | Football field- home bleachers | ADA |
| 142456 | Paint Branch High School | Athletic Field | Exterior Access Route | Exterior Accessible Route | 1 | The accessible route has running slopes greater than 1:20 (5%). | Football field - visitors bleachers | ADA |
| 142356 | Paint Branch High School | Exterior | Exterior Access Route | Curb Ramp | 1 | The parallel curb ramp landing is not compliant. | Curb Ramp CR-1 | ADA |
| 142357 | Paint Branch High School | Exterior | Exterior Access Route | Exterior Accessible Route | 1 | A compliant turning space is not provided at a change of direction. | Entrance to tennis courts from curb ramp one (CR-1) | ADA |
| 142443 | Paint Branch High School | Exterior | Exterior Access Route | Exterior Accessible Route | 1 | The accessible route has cross slopes greater than 1:50 (2%). | Sidewalk between ticket booth and track entrance | ADA |
| 142444 | Paint Branch High School | Exterior | Exterior Access Route | Exterior Accessible Route | 1 | The accessible route has cross slopes greater than 1:50 (2%). | Between the track and the football bleachers | ADA |
| 142445 | Paint Branch High School | Exterior | Exterior Access Route | Ramp | 1 | The ramp running slope exceeds 1:12 (8.33%). | Ramp R-1 | ADA |
| 142446 | Paint Branch High School | Exterior | Exterior Access Route | Ramp | 1 | The ramp run has a rise greater than 6"; however, handrails are not provided. | Ramp R-1 | ADA |
| 142472 | Paint Branch High School | Exterior | Exterior Access Route | Stairs | 1 | Handrails are not provided. | Door D20 | ADA |
| 142475 | Paint Branch High School | Exterior | Exterior Access Route | Curb Ramp | 1 | The slope of the curb ramp flare is greater than 1:10 (10%). | Curb Ramp CR-6 | ADA |
| 142476 | Paint Branch High School | Exterior | Exterior Access Route | Exterior Accessible Route | 1 | The accessible route has cross slopes greater than 1:50 (2%). | 35 feet North of curb ramp CR-7 | ADA |
| 142477 | Paint Branch High School | Exterior | Exterior Access Route | Exterior Accessible Route | 1 | A compliant turning space is not provided at a change of direction. | Door D-22 | ADA |
| 142478 | Paint Branch High School | Exterior | Exterior Access Route | Exterior Accessible Route | 1 | The walkway has areas with greater than 1:20 (5%) running slope. | Between Doors D22 & Curb Ramp CR-8 | ADA |
| 142483 | Paint Branch High School | Exterior | Exterior Access Route | Curb Ramp | 1 | The curb ramp does not meet the slope requirements. | Curb Ramp CR-11 | ADA |
| 142484 | Paint Branch High School | Exterior | Exterior Access Route | Exterior Accessible Route | 1 | The accessible route has cross slopes greater than 1:50 (2%). | Outside Door D28 | ADA |
| 142485 | Paint Branch High School | Exterior | Exterior Access Route | Building Entrance - Door | 1 | The maneuvering clearance at the accessible door is not level and clear. | Door D-32 | ADA |
| 142488 | Paint Branch High School | Exterior | Exterior Access Route | Curb Ramp | 1 | A curb ramp is not provided where the accessible route crosses a curb. | Proposed Curb Ramp CR-A | ADA |

| Id | Facility | Building | Assembly | Type | Barrier Priority | Detail | Location Description | ADA |
|--------|--------------------------|----------------|-------------------------|---------------------------|------------------|---|--|-------------------|
| 142378 | Paint Branch High School | Interior | Common Areas | Interior Door | 1 | The accessible door with door closer has a sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. | Main Office and College Office hallway door | ADA |
| 142402 | Paint Branch High School | Interior | Interior Access Route | Door | 1 | The pull side of the accessible door does not have the required maneuvering clearances. | Room 2328 | ADA |
| 142403 | Paint Branch High School | Interior | Interior Access Route | Door | 1 | The push side of the accessible door does not have the required maneuvering clearances. | Room 2328 | ADA |
| 142432 | Paint Branch High School | Interior | Interior Access Route | Ramp | 1 | Handrails do not extend 12" horizontally beyond the top and bottom of ramp runs above the landing surface. | Auditorium - 1016 | ADA |
| 142433 | Paint Branch High School | Interior | Interior Access Route | Ramp | 1 | The ramp running slope exceeds 1:12 (8.33%). | Auditorium - 1016 | ADA |
| 142434 | Paint Branch High School | Interior | Interior Access Route | Ramp | 1 | The ramp has a rise greater than 6"; however, handrails are not provided. | Auditorium - 1016 | ADA |
| 142435 | Paint Branch High School | Interior | Interior Access Route | Platform Lift | 1 | The platform lift is not compliant. | Auditorium -1016 | ADA |
| 142436 | Paint Branch High School | Interior | Interior Access Route | Platform Lift | 1 | The platform lift is not compliant. | Auditorium -1016 | ADA |
| 142437 | Paint Branch High School | Interior | Interior Access Route | Stairs | 1 | Handrails are not compliant. | Auditorium -1016 | ADA |
| 142438 | Paint Branch High School | Interior | Interior Access Route | Ramp | 1 | The ramp running slope exceeds 1:12 (8.33%). | Auditorium -1016 | ADA |
| 143110 | Paint Branch High School | Interior | Interior Access Route | Vertical Level Change | 1 | Vertical level changes between 1/4" and 1/2" high are not beveled or vertical level changes greater than 1/2" high are not ramped. | Weight Room | ADA |
| 142359 | Paint Branch High School | Parking Lot | Accessible Parking | Parking Space - Car | 1 | Compliant signage is not provided at the standard accessible space. | Accessible Parking Space P14-B | ADA |
| 142360 | Paint Branch High School | Parking Lot | Accessible Parking | Parking Space - Van | 1 | Compliant signage is not provided at the van space. | Accessible Parking Space P14-A | ADA |
| 142361 | Paint Branch High School | Parking Lot | Accessible Parking | Parking Space-Van | 1 | MARYLAND: A van access aisle is not provided. | Accessible Parking Space P14-A | State of Maryland |
| 142362 | Paint Branch High School | Parking Lot | Exterior Access Route | Exterior Accessible Route | 1 | A compliant accessible route is not provided from the public access to the amenity. | Accessible Parking Spaces P14 A and B | ADA |
| 142486 | Paint Branch High School | Parking Lot | Accessible Parking | Parking Space - Van | 1 | The parking space slope is greater than 1:50 (2%). | Accessible Parking Space P12-A | ADA |
| 142487 | Paint Branch High School | Parking Lot | Accessible Parking | Parking Space - Van | 1 | The parking space slope is greater than 1:50 (2%). | Accessible Parking Space P12-B | ADA |
| 142489 | Paint Branch High School | Parking Lot | Accessible Parking | Parking Space - Van | 1 | The parking space slope is greater than 1:50 (2%) and gaps greater than 1/2" | Accessible Parking Space P5-A | ADA |
| 142490 | Paint Branch High School | Parking Lot | Accessible Parking | Parking Space - Van | 1 | The parking space slope is greater than 1:50 (2%). | Accessible Parking Space P5-B | ADA |
| 142491 | Paint Branch High School | Parking Lot | Accessible Parking | Parking Space - Van | 1 | The access aisle has a slope more than 1:50 (2%). | Accessible Parking Space P5-A | ADA |
| 142492 | Paint Branch High School | Parking Lot | Accessible Parking | Parking Space - Car | 1 | The slope of the parking space is greater than 1:50 (2%). | Accessible Parking Space P5-C | ADA |
| 143861 | Paint Branch High School | Parking Lot | Accessible Parking | Parking Spaces-General | 1 | The minimum number of accessible parking spaces is not provided. | Parking Lot 1 | ADA |
| 142494 | Paint Branch High School | Playground | Exterior Access Route | Exterior Accessible Route | 1 | Sidewalk has areas of vertical level changes in excess of 1/4" that are not ramped. | Playground 2 | ADA |
| 142460 | Paint Branch High School | Restroom | Exterior Access Route | Door | 1 | The door does not have the required maneuvering clearances. | Student restroom 5022 & 5023 at the football field | ADA |
| 142463 | Paint Branch High School | Restroom | Exterior Access Route | Door | 1 | The accessible door with door closer has a sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. | Men's Restroom 5022 & Women's Restroom 5023 | ADA |
| 142465 | Paint Branch High School | Athletic Field | Exterior Access Route | Gate | 2 | The swinging gate does not have a smooth surface within 10" of the ground. | Baseball field bleachers | ADA |
| 142470 | Paint Branch High School | Athletic Field | Baseball/Softball Field | Player Seating | 2 | A wheelchair space is not provided at each team bench area at the ball field. | Baseball Visitor Bench | ADA |
| 143107 | Paint Branch High School | Athletic Field | Common Areas | Assembly Area | 2 | The assistive listening device is not compliant or is not provided. | Football Field | ADA |
| 143108 | Paint Branch High School | Athletic Field | Football Field | Player Seating | 2 | A wheelchair space is not provided at each team seating for the football field. | Football Field | ADA |
| 142451 | Paint Branch High School | Athletic Field | Exterior Access Route | Gate | 2 | The swinging gate does not have a smooth surface within 10" of the ground. | Softball field bleachers | ADA |

| Id | Facility | Building | Assembly | Type | Barrier Priority | Detail | Location Description | ADA |
|--------|--------------------------|----------------|-----------------------|-------------------------|------------------|--|---|-----|
| 142454 | Paint Branch High School | Athletic Field | Exterior Access Route | Gate | 2 | The swinging gate does not have a smooth surface within 10" of the ground. | Track and basketball gates | ADA |
| 142358 | Paint Branch High School | Exterior | Exterior Access Route | Gate | 2 | The swinging gate does not have a smooth surface within 10" of the ground. | Tennis Courts | ADA |
| 143109 | Paint Branch High School | Exterior | Common Areas | Dining And Work Surface | 2 | A minimum of 5% ADA compliant dining seating and standing spaces are not provided. | Exterior Dining Tables | ADA |
| 142365 | Paint Branch High School | Interior | Interior Access Route | Signage | 2 | The existing signage is not mounted at a compliant height. | First floor egress doors | ADA |
| 142366 | Paint Branch High School | Interior | Interior Access Route | Signage | 2 | Tactile room identification signage is not provided at both entrances, where more than one entrance is provided. | Back door to Auxiliary Gym Room 1003 | ADA |
| 142367 | Paint Branch High School | Interior | Interior Access Route | Signage | 2 | The provided signage is not mounted at a compliant location. | Weight Room 1103 | ADA |
| 142369 | Paint Branch High School | Interior | Interior Access Route | Signage | 2 | The provided signage is not mounted at a compliant height. | Main Office Suites | ADA |
| 142370 | Paint Branch High School | Interior | Interior Access Route | Signage | 2 | Tactile room identification signage is not provided at both entrances, where more than one entrance is provided. | Staff Work Room in Main Office | ADA |
| 142387 | Paint Branch High School | Interior | Interior Access Route | Reach Range | 2 | The vending machine has operable parts which are not compliant. | 1600 hallway vending machine | ADA |
| 142394 | Paint Branch High School | Interior | Interior Access Route | Signage | 2 | The provided signage is not mounted at the latch side of the door or at a compliant height. | Second entrance to rooms 3003, 3006, 3107, 3110, 3111 3214, 3317, 3318, 3220, 3323,3228, 3226 , | ADA |
| 142399 | Paint Branch High School | Interior | Interior Access Route | Signage | 2 | The provided signage is not mounted at a compliant height. | 2nd floor room identification signs | ADA |
| 142400 | Paint Branch High School | Interior | Common Areas | Work Surface | 2 | The work surface height is not compliant. Knee and toe clearances are not provided. | Media Center - 2010 | ADA |
| 142401 | Paint Branch High School | Interior | Common Areas | Service Counter | 2 | The service counter height is greater than 36". | Media Center - 2010 | ADA |
| 142404 | Paint Branch High School | Interior | Interior Access Route | Signage | 2 | The provided signage is not mounted at the latch side of the door or at a compliant height. | TV Studio 2nd door to 2100 suites, 2403, 2006 | ADA |
| 142408 | Paint Branch High School | Interior | Interior Access Route | Signage | 2 | Tactile room identification signage is not provided at both entrances, where more than one entrance is provided. | Second Door to rooms 1205, 1142, 1215, 1223, 1229, Johnston Hall 1400 - all 3 doors | ADA |
| 142409 | Paint Branch High School | Interior | Interior Access Route | Signage | 2 | The provided signage is not mounted at a compliant height. | First floor doors with closers | ADA |
| 142416 | Paint Branch High School | Interior | Kitchen | Kitchen | 2 | Less than minimum one of each type of operable part is within reach range. | Room 1142 | ADA |
| 142417 | Paint Branch High School | Interior | Kitchen | Kitchen | 2 | Less than minimum one of each type of operable part is within reach range. | Room 1142 | ADA |
| 142418 | Paint Branch High School | Interior | Common Areas | Work Surface | 2 | The work surface height is not compliant. Knee and toe clearances are not provided. | Room 1344E | ADA |
| 142419 | Paint Branch High School | Interior | Common Areas | Work Surface | 2 | The work surface height is not compliant. Knee and toe clearances are not provided. | Room 1344E | ADA |
| 142420 | Paint Branch High School | Interior | Common Areas | Work Surface | 2 | The work surface height is not compliant. Knee and toe clearances are not provided. | Room 1344C | ADA |
| 142439 | Paint Branch High School | Interior | Interior Access Route | Signage | 2 | Means of egress signage does not have tactile lettering and is not located adjacent the latch side of the door.. | Auditorium -1016 | ADA |
| 142990 | Paint Branch High School | Interior | Common Areas | Work Surface | 2 | The work surface height is not compliant. Knee and toe clearances are not provided. | Room 1344C | ADA |
| 142493 | Paint Branch High School | Playground | Exterior Access Route | Gate | 2 | The swinging gate does not have a smooth surface within 10" of the ground. | Playground 2 | ADA |
| 143040 | Paint Branch High School | Playground | Playground | Transfer System | 2 | The transfer platform for connecting to elevated play elements has non-compliant dimensions. | Playground 1 | ADA |
| 143041 | Paint Branch High School | Playground | Playground | Ground Surface-Fibar | 2 | The ground surface has not been inspected and maintained regularly. | Playground 2 | ADA |



| Id | Facility | Building | Assembly | Type | Barrier Priority | Detail | Location Description | ADA |
|--------|--------------------------|----------------|-----------------------|------------------------------------|------------------|---|--|-----|
| 143042 | Paint Branch High School | Playground | Playground | Transfer System | 2 | The transfer platform for connecting to elevated play elements has non-compliant dimensions. | Playground 2 | ADA |
| 142447 | Paint Branch High School | Athletic Field | Common Areas | Assembly Area | 3 | Assembly areas do not provide wheelchair spaces. | Softball field bleachers | ADA |
| 142450 | Paint Branch High School | Athletic Field | Exterior Access Route | Exterior Accessible Route | 3 | A compliant accessible route is not provided. | Softball field- visitors team bench | ADA |
| 142363 | Paint Branch High School | Interior | Common Areas | Assembly Area | 3 | Assembly areas do not provide wheelchair spaces. | Gym 1 | ADA |
| 142377 | Paint Branch High School | Interior | Interior Access Route | Door | 3 | The opening force of the interior hinged non-fire door is more than 5#s. | Main Office and College Office hallway door | ADA |
| 142388 | Paint Branch High School | Interior | Restroom | Restroom / Bathroom - Signage | 3 | The provided signage is not mounted at the latch side of the door or at a compliant height. | 3rd floor doors | ADA |
| 142389 | Paint Branch High School | Interior | Interior Access Route | Door | 3 | The accessible door with door closer has a sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. | 3rd floor doors with closers | ADA |
| 142390 | Paint Branch High School | Interior | Interior Access Route | Door | 3 | The opening force of the interior hinged door non- fire door is more than 5#s. | 3rd floor doors with closers | ADA |
| 142397 | Paint Branch High School | Interior | Interior Access Route | Door | 3 | The opening force of the interior hinged non-fire door is more than 5#s. | 2nd floor doors with closers | ADA |
| 142398 | Paint Branch High School | Interior | Interior Access Route | Door | 3 | The accessible door with door closer has a sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. | 2nd floor doors with closers | ADA |
| 142406 | Paint Branch High School | Interior | Interior Access Route | Door | 3 | The opening force of the interior, hinged non-fire door is more than 5#s. | 1st floor doors with closers | ADA |
| 142407 | Paint Branch High School | Interior | Interior Access Route | Door | 3 | The accessible door with door closer has a sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. | 1st floor doors with closers | ADA |
| 142429 | Paint Branch High School | Interior | Common Areas | Assembly Area | 3 | An assistive listening device is not provided. | Auditorium 1016 | ADA |
| 142430 | Paint Branch High School | Interior | Common Areas | Assembly Area | 3 | Assembly areas do not provide compliant aisle seats. | Auditorium -1016 | ADA |
| 142431 | Paint Branch High School | Interior | Common Areas | Assembly Area | 3 | Assembly areas do not provide wheelchair spaces. | Auditorium - 1016 | ADA |
| 142473 | Paint Branch High School | Interior | Interior Access Route | Signage | 3 | Area of refuge instruction signage is not provided. | Stairs 1 thru 5 at floors 2 and 3 | ADA |
| 142474 | Paint Branch High School | Interior | Interior Access Route | Signage | 3 | Means of egress signage is not provided. | Stairs 1 thru 5 at floors 2 and 3 | ADA |
| 142380 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Mirror | 3 | The bottom of the reflective surface of the mirror is mounted higher than 35" where it is not located over a counter or lavatory. | Girls Restroom 1019 | ADA |
| 142381 | Paint Branch High School | Restroom | Restroom | Restroom/Bathroom-Door | 3 | The opening force of the interior, hinged, non-fire door is more than 5 pounds. | Boys Restroom 1013, Girls Restroom 1019 | ADA |
| 142382 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Signage | 3 | The provided signage is not mounted at a compliant height. | Boys Restroom 1013, Girls Restroom 1019 | ADA |
| 142383 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Mirror | 3 | The bottom of the reflective surface of the mirror is mounted higher than 35", where it is not located above a counter or lavatory. | Boys Restrooms: 1032, 1120, 1140, 2020, 2121, Girls Restrooms: 1034, 1122, 1138, 2119, 2022 | ADA |
| 142384 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Lavatory | 3 | Pipes are not insulated. | Boys Restrooms: 1032, 1120, 1140, 2020, 2121, Girls Restrooms: 1034, 1122, 1138, 2119, 2022 | ADA |
| 142385 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom | 3 | Controls are not within an allowable reach range. | Boys Restroom 1013 | ADA |
| 142386 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Signage | 3 | The provided signage is not mounted at the latch side of the door or at a compliant height. | Boys Restrooms: 1032, 1120, 1140, 2020, 2121, Girls Restrooms: 1034, 1122, 1138, 2119, 2022, Preschool 1030, Student 1201B | ADA |
| 142395 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Toilet Stall | 3 | The wheelchair stall door is not compliant. | Boys Restroom 1032, 1120, 1140, 2121, Girls Restroom 1034, 1138, 2119, 2022 | ADA |

| Id | Facility | Building | Assembly | Type | Barrier Priority | Detail | Location Description | ADA |
|--------|--------------------------|----------|-----------------------|---|------------------|--|---|-----|
| 142396 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Signage | 3 | The provided signage is not mounted at a compliant height. | Staff Restroom 1323, 2316, 2318, 3004, 3008 | ADA |
| 142411 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Lavatory | 3 | The lavatory is mounted higher than 34" to the higher of the rim or counter. | Student Restroom 1201B, 1200A | ADA |
| 142423 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Toilet Stall | 3 | The side grab bar is not compliant in the wheelchair stall. | Girls Restroom 3018 | ADA |
| 142427 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Door | 3 | The opening force of the interior, non-fire, hinged, sliding, and folding door or gate is more than 5 pounds. | Boys Restrooms: 1032, 1120, 1140, 2020, 2121, Girls Restrooms: 1034, 1122, 1138, 2119, 2022 | ADA |
| 142428 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Door | 3 | The accessible door with door closer has a sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. | Boys Restrooms: 1032, 1120, 1140, 2020, 2121, Girls Restrooms: 1034, 1122, 1138, 2119, 2022 | ADA |
| 142440 | Paint Branch High School | Restroom | Restroom | Restroom/Bathroom-Locker | 3 | The locker area does not have accessible lockers. | Boy's locker room 1609 | ADA |
| 142441 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Transfer Shower Stall | 3 | The transfer shower is not exactly 36" by 36". | Boy's Locker Room 1609, Girls Locker Room 1605 | ADA |
| 142442 | Paint Branch High School | Restroom | Restroom | Restroom/Bathroom-Water Closet | 3 | The centerline of the toilet in the wheelchair stall is not 16" minimum to 18" maximum from the sidewall. | Boy's Locker Room 1613B, Girl's Locker Room 1601G | ADA |
| 142461 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Lavatory | 3 | Pipes are not insulated. | Men's Restroom 5022 and Women's Restroom 5023 at football field | ADA |
| 142462 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Toilet Stall | 3 | The wheelchair stall door is not compliant. | Women's Restroom 5023 at football field | ADA |
| 142963 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Mirror | 3 | The bottom of the reflective surface of the mirror is mounted higher than 35", where not located above a counter or lavatory. | Boys Restrooms: 2100, 3016, 3104 Girls Restrooms: 2102, 3018, 3102 | ADA |
| 142964 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Lavatory | 3 | Pipes are not insulated. | Boys Restrooms: 2100, 3016, 3104 Girls Restrooms: 2102, 3018, 3102 | ADA |
| 142965 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Signage | 3 | The provided signage is not mounted at a compliant height. | Boys Restrooms: 2100, 3016, 3104 Girls Restrooms: 2102, 3018, 3102 | ADA |
| 142966 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Toilet Stall | 3 | The wheelchair stall door is not compliant. | Boys Restrooms 3014, 3016 Girls Restrooms 3018, 3102 | ADA |
| 142969 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Door | 3 | The opening force of the interior, non-fire, hinged door is more than 5 pounds. | Boys Restrooms: 2100, 3016, 3104 Girls Restrooms: 2102, 3018, 3102 | ADA |
| 142970 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Door | 3 | The accessible door with door closer has a sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. | Boys Restrooms: 2100, 3016, 3104 Girls Restrooms: 2102, 3018, 3102 | ADA |
| 142971 | Paint Branch High School | Restroom | Restroom | Restroom/Bathroom-Locker | 3 | The locker area does not have accessible lockers. | Girl's Locker Room 1605 | ADA |
| 142972 | Paint Branch High School | Restroom | Restroom | Restroom/Bathroom-Locker | 3 | The locker area does not have accessible lockers. | Team Locker Room 2 (Room 1601B) | ADA |
| 142973 | Paint Branch High School | Restroom | Restroom | Restroom/Bathroom-Locker | 3 | The locker area does not have accessible lockers. | Team Locker Room 1 (Room 1601A) | ADA |
| 143112 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Transfer Shower Stall | 3 | The transfer shower is not exactly 36" by 36". | Coach's Locker Room 1605C, 1609E | ADA |
| 142364 | Paint Branch High School | Interior | Interior Access Route | Drinking Fountain / Water Cooler | 4 | Knee and toe clearance is not provided at the lower level fountain. | Drinking Fountains DF1 through DF8 | ADA |
| 142410 | Paint Branch High School | Interior | Interior Access Route | Drinking Fountain / Water Cooler | 4 | The minimum number of drinking fountains is not provided. If the minimum number is provided, two levels or a hi-lo are not provided. If more than 2 are provided, less than 50% are high or less than 50% are low. | Room 1030 | ADA |
| 142415 | Paint Branch High School | Interior | Kitchen | Kitchen - Oven | 4 | The oven door is not located adjacent to a minimum 30" wide work surface. | Room 1142 | ADA |

| Id | Facility | Building | Assembly | Type | Barrier Priority | Detail | Location Description | ADA |
|--------|--------------------------|----------|-----------------------|------------------------------------|------------------|---|--|-----|
| 143111 | Paint Branch High School | Interior | Common Areas | Locker Rooms | 4 | The locker room does not have at least one of the shelves at 15" minimum and 48" maximum height. | Hallway Lockers | ADA |
| 142479 | Paint Branch High School | Exterior | Exterior Access Route | Ramp | 5 | The ramp running slope exceeds 1:12 (8.33%). | Loading Dock Ramp R-2 | ADA |
| 142480 | Paint Branch High School | Exterior | Exterior Access Route | Ramp | 5 | The ramp has a rise greater than 6"; however, handrails and edge protection are not provided. | Loading Dock Ramp R2 | ADA |
| 142481 | Paint Branch High School | Exterior | Exterior Access Route | Stairs | 5 | Steps do not have uniform and compliant riser heights and/or tread depths. | Loading Dock Stair ST-6 | ADA |
| 142371 | Paint Branch High School | Interior | Kitchen | Sink | 5 | Sinks do not have knee and/or toe clearance. | Staff Work Room in the Main Office | ADA |
| 142372 | Paint Branch High School | Interior | Interior Access Route | Reach Range | 5 | The vending machines have operable parts which are not within reach range. | Staff Work Room in the Main Office | ADA |
| 142375 | Paint Branch High School | Interior | Interior Access Route | Door | 5 | The opening force of the interior hinged door non-fire door is more than 5#s. | Office Hallway | ADA |
| 142376 | Paint Branch High School | Interior | Interior Access Route | Door | 5 | The opening force of the interior hinged door non- fire door is more than 5#s. | Staff Work Room | ADA |
| 142391 | Paint Branch High School | Interior | Kitchen | Appliance | 5 | Clear floor space at all sinks, works surfaces, operable parts and appliances is not provided. | Staff workroom 2203, 3217 | ADA |
| 142373 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Water Closet | 5 | The toilet paper dispenser is not at a compliant location. | Staff Restroom 1000R | ADA |
| 142374 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Lavatory | 5 | The lavatory is mounted higher than 34" to the higher of the rim or counter. | Staff2 | ADA |
| 142392 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Lavatory | 5 | The lavatory is mounted higher than 34" to the higher of the rim or counter. | Staff Restroom 1038I, 1323, 1400B, 1609cC, 1609E, 2316, 3004, 3008 | ADA |
| 142393 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Lavatory | 5 | Pipes are not insulated. | Staff Restrooms 2318,3008 | ADA |
| 142412 | Paint Branch High School | Restroom | Common Areas | Locker Rooms | 5 | The locker room does not have a compliant bench. | Staff Locker rooms 1038H and 1222B | ADA |
| 142413 | Paint Branch High School | Restroom | Common Areas | Locker Rooms | 5 | The locker room does not have accessible lockers. | Staff Locker Rooms 1038H and 1222B | ADA |
| 142414 | Paint Branch High School | Restroom | Interior Access Route | Door | 5 | The door does not have the required maneuvering clearances. | Student Restroom 1200A | ADA |
| 142422 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Water Closet | 5 | The water closet does not have the required clearance. | Staff Restroom1222B,1400B | ADA |
| 142424 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Door | 5 | The opening force of the interior, non-fire, hinged door is more than 5 pounds. | Staff Restroom 1223, 1038I, 1400B, 2316, 2318, 3004, 3008 | ADA |
| 142425 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Door | 5 | The accessible door with door closer has a sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. | Staff Restroom 1223, 1038I, 1400B, 2316, 2318, 3004, 3008 | ADA |
| 142426 | Paint Branch High School | Restroom | Restroom | Restroom / Bathroom - Coat Hook | 5 | The coat hook is not within an allowable reach range. | Staff Restroom 1222B, 2318 | ADA |