SECTION 26 0101

ELECTRICAL GENERAL PROVISIONS

PART 1 - GENERAL

1.1 SECTION INCLUDES

A. General provisions and requirements for electrical work.

1.2 RELATED SECTIONS

A. Requirements of this section generally supplement requirements of Division 01.

1.3 REFERENCES

A. NFPA 10: Portable Fire Extinguishers.

B. NFPA 241: Safeguarding Construction, Alteration, and Demolition Operations.

1.4 SYSTEM DESCRIPTION

A. The full set of Contract Documents applies to work of Divisions 26 and 28.

B. Visit the site and study aspects of the project and working conditions, as required by General and Supplementary Conditions, Bidding and Contracting Requirements, Drawings, and Specifications. Verify field dimensions.

C. The work covered in technical sections includes the furnishing of labor, equipment and materials, and the performance of operations pertinent to the work described.

D. Except as required otherwise in Division 01, promptly obtain and pay for necessary signatures and paperwork, permits, fees and inspections required for work of this division by authorities having jurisdiction, including any utility connection or extension charge. No payment will be made until a copy of the permit is forwarded to the Owner.

E. Electrical work of this project includes, as a brief general description, the following:

1. Work shall be performed over two summer periods.
2. First summer work shall include the following:

    a. Provide conduits and raceways for new generator.
    b. Provide conduits and raceways for new devices and connections to existing equipment. Final connections to new devices and existing equipment shall be performed during the second summer.
    c. Provide new concrete pad for new generator.
    d. Connect lighting fixtures in toilet rooms on normal circuits to existing emergency lighting circuits, where indicated on drawings.

3. Second summer shall include the following:

    a. Provide new generator and associated equipment.
    b. Connect existing boilers and associated pumps to the new standby panelboard.
    c. Connect existing kitchen refrigeration equipment to new standby panelboard.
    d. Connect existing intercommunications/public address system to the new standby panelboard.

e. Connect existing main telecom room receptacles to the new standby panelboard.
f. Connect normal lighting fixtures in the main mechanical room/boiler room and main electrical room to the new emergency panelboard.
g. Connect lighting fixtures in toilet rooms on normal circuits to the new emergency panelboard, where indicated on drawings.

F. See Division 01 for requirements related to Owner's occupancy of the premises, limits on use of site, time restrictions on work, limits on utility outages or shutdowns, and phasing (sequencing) and scheduling.

1.5 PRODUCT OPTIONS

A. Except as modified by provisions of Bidding and Contracting Requirements and Division 01, these options apply to Division 26 and 28 specifications.

B. General: Where Contractor is permitted to use a product other than the specified item and model named as the basis of design, Contractor is responsible for coordination and additional costs as specified in article "Substitutions" below for substitutions.

C. Products specified by reference standards or by description only: Any product meeting those standards or description.

D. Products specified by naming one or more manufacturers, or model name or catalog reference number: Products specified establish a standard of quality, options to be included, and performance.

1. Where other acceptable manufacturers are named, Contractor may provide products of those named manufacturers only, which meet the specifications.
2. Where specification permits "equal" products, without naming other acceptable manufacturers, Contractor may use products of any manufacturer, which meet the specifications.

E. Products specified by naming one manufacturer and particular product, with no provision for other options: No options or substitutions allowed.

1.6 SUBSTITUTIONS

A. Substitutions will be considered only as permitted or required by the Bidding and Contracting Requirements and Division 01. Except as modified by those requirements, the requirements below apply to Division 26 and 28 specifications.

B. Substitutions may be considered when a product becomes unavailable through no fault of the Contractor.

C. Document each request with complete data substantiating compliance of proposed substitution with contract documents.

D. A request constitutes a representation that the Bidder or Contractor:

1. Has investigated proposed product and determined that it meets or exceeds the quality level of the specified product.
2. Will provide the same warranty for the substitution as for the specified product.
3. Will coordinate installation and make changes to other work which may be required for the work to be complete with no additional cost to Owner.
4. Waives claims for additional costs or time extension which may subsequently become apparent.

©2023 James Posey Associates, Inc. 7753-22

5. Will reimburse Owner for review or redesign services associated with re-approval by authorities.

E. Substitutions will not be considered when they are indicated or implied on shop drawing or product data submittals, without separate written request, or when acceptance will require revision to the Contract Documents.

F. Substitution submittal procedure is specified in Bidding and Contracting Requirements and Division 01.

1.7 MATERIALS AND EQUIPMENT

A. Materials and equipment shall be new and the best of their respective kinds, suitable for the conditions and duties imposed on them by the project, and of representative manufacturer. The description, characteristics and requirements of the materials to be used shall be in accordance with the specifications.

B. Equipment, construction and installation must meet requirements of local, state and federal governing codes.

C. Singular number: In cases where material, a device, or part of the equipment is referred to in the singular number in the specifications, it is intended that such reference shall apply to as many items of material, devices, or parts of the equipment as are required to complete the installation as shown on the drawings or required for proper operation of the system.

D. Terms have the following meanings:

1. Furnish: Supply item
2. Install: Mount and connect item
3. Provide: Furnish and install

E. Materials and equipment shall be installed and completed in a first class and workmanlike manner and in accordance with the best modern methods, practice and manufacturers' instructions. Any work which shall not present an orderly and neat or workmanlike appearance shall be removed and replaced with satisfactory work when so directed in writing by the Architect.

F. The specifications and drawings are intended to define the minimum requirements, as to quality of materials, construction, finish and overall workmanship.

G. General Conditions describe the correlation and intent of the Contract Documents. In case of discrepancies between the specifications and drawings, the specifications should be followed as to the general methods and principles and the drawings followed as to sizes, capacities and specifics for corresponding parts. If sizes are omitted, the Architect will determine sizes to be utilized.

H. In cases of doubt, uncertainty, or conflict as to the true meaning of the specifications or drawings, it is the responsibility of the Contractor to notify the Architect of said uncertainty, doubt, or conflict and obtain a decision as to the intent prior to initiating any work which may be affected by this decision.

1.8 COORDINATION

A. Should a situation develop during construction to prevent the proper installation of any equipment or item where shown on the drawings, call the situation to the attention of the Architect and await a written decision.

B. Plan and coordinate work to proceed in an orderly and continuous manner without undue delay, and in conformance with the project schedule. Submit samples, shop drawings, schedules, insurance policies and certificates, and the like in time to avoid delays in actual construction. Coordinate electrical work so that work of each trade is completed before other construction begins which would obstruct it.

C. Coordinate trades to ensure that proper clearances between work of the various trades allow access to items which require operation and maintenance.

D. Coordinate location and elevation of conduit, light fixtures, equipment, and appurtenances in such a manner that the finished installation is as indicated on drawings. In the event difficulties are encountered which prevent this, it is the Contractor's responsibility to bring this to the attention of the Architect prior to initiation of work. Correct improperly coordinated installation at no additional cost.

E. The Contractors' assistants shall include a competent electrical foreman, who shall be on the premises at all times to check, layout, coordinate and superintend the installation of work. The foreman shall establish basic requirements relative to the work before starting, and be responsible for the accuracy thereof.

1.9 SUBMITTALS

A. Manufacturers' and subcontractors' lists:

1. As specified in Division 01, submit a complete list of proposed manufacturers for equipment, materials and subcontractors used for the work of this division. Lists shall follow the sequence of the specifications. No considerations will be given for partial or incomplete lists. After review of lists, submit shop drawings and product data.

B. Shop drawings and product data:

1. Submit in accordance with the requirements of Division 01 or as established at the preconstruction conference, the required number of copies of Shop Drawings and Product Data for every item of equipment. Shop drawings or product data will not be considered until Manufacturers' Lists have been approved. Shop drawings and product data shall be submitted, as required by the General Conditions, with sufficient time for checking, return to Contractor, and resubmission as required before Contractor shall install any item.
2. Each item submitted shall be properly labeled, indicating the specific service for which the equipment or material is to be used, section and paragraph number of specification or drawing number to which it applies, Contractor's name and project name and number. Data submitted shall be specific and shall include product data and printed information in sufficient detail and scope to verify compliance with requirements of the contract documents. Clearly identify each item within the data. Data of a general nature will not be accepted. Each sheet must clearly show the project name and number.
3. The review of a shop drawing or product data shall not be considered as a guarantee of the measurements or building conditions or that the shop drawings or product data have been checked to see that item submitted properly fits the building conditions. This review shall not relieve the Contractor of the responsibility for furnishing material or performing work as required by the contract documents, for correctness of dimensions and quantities, or for proper coordination of details and interfaces among trades.
4. Exclusively electrical items furnished as items associated with mechanical items but not specifically described in the mechanical item submission, shall be submitted as a separate submittal but shall be clearly marked as associated with the mechanical item by identified specification paragraph.
5. Product data sheets shall be 8.5-inches by 11-inches cut sheets for operating and maintenance manual.

©2023 James Posey Associates, Inc. 7753-22

C. Submit at least three copies of the results of every test required under any section in this division.

D. Specialist shall submit a list of at least three projects similar to this project in type, size, and quality, which have been in place and operating satisfactorily for at least five years.

   1. Include project name, address, name and phone number of owner's representative, and project type and size.

E. After the work is completed, submit required certificates of approval from approved inspection agencies and authorities having jurisdiction over work of this division. Certificates of approval must be received by the Architect prior to final acceptance of the work.

1.10 SPECIALIST

A. The term "Specialist" as used in the specification shall mean an individual or firm of established reputation (or, if newly organized, whose personnel have previously established a reputation in the same field,) which is regularly engaged in, and which maintains a regular force of workers skilled in either (as applicable) manufacturing or fabricating items required by the contract, installing items required by the contract, or otherwise performing work required by the contract. Where the specification requires installation by a specialist, the term shall also be deemed to mean the manufacturer of the item, an individual or firm licensed by the manufacturer, or an individual or firm who will perform the work under the manufacturer's direct supervision.

1.11 CONTRACT CLOSEOUT SUBMITTALS

A. Project record documents:

   1. Maintain on site one set of the following record documents; record actual revisions to the work of this division:

      a. Contract Drawings.
      b. Specifications.
      c. Addenda.
      d. Change Orders and other Modifications to the Contract.
      e. Reviewed shop drawings, product data, and samples.

   2. Maintain record documents separate from documents used for construction.
   3. Record information concurrent with construction progress.
   4. Specifications: Legibly mark and record in each section a description of actual products installed, including the following:

      a. Manufacturer's name and product model and number.
      b. Product options, substitutions, or alternates utilized.
      c. Changes made by addenda and modifications.

   5. Record documents and shop drawings: Legibly mark each item to record actual construction, including:

      a. Measured locations of internal utilities and appurtenances concealed in construction, referenced to visible and accessible features of the work.
      b. Field changes of dimension and detail.
      c. Details not on original Contract Drawings.

   6. Submit documents as specified in Division 01.

B. Operation and maintenance data:

1. Submit sets prior to final inspection as specified in Division 01. Unless otherwise specified in Division 01, submit no fewer than three sets. In addition to requirements specified in Division 01, submit operating and maintenance manuals for the work of this division as specified below.
2. Prepare covers with printed title “OPERATION AND MAINTENANCE INSTRUCTIONS,” and title of project
3. Internally subdivide the contents with permanent page dividers, logically organized as described below.
4. Contents: Prepare a Table of Contents, with each product or system description identified.
5. Part 1: Directory, listing names, addresses, and telephone numbers of electrical engineers; contractor; electrical subcontractors; and major electrical equipment suppliers.
6. Part 2: Operation and maintenance instructions, arranged by specification section. For each category, identify names, addresses, and telephone numbers of subcontractors and suppliers. Identify the following:

    a. Significant design criteria.
    b. List of equipment.
    c. Parts list for each component, including recommended spare parts list.
    d. Operating instructions.
    e. Maintenance instructions for equipment and systems.
    f. Maintenance instructions for special finishes, including recommended cleaning methods and materials and special precautions identifying detrimental agents.

7. Part 3: Project documents and certificates, including the following:

    a. Shop drawings and product data.
    b. Photocopies of certificates.
    c. Photocopies of warranties, guarantees, and bonds.
    d. Test reports: Copies of the results of tests required under sections of specifications.
    e. Photocopies of each panelboard circuit directory or directories for each panelboard provided, including panel name, panel location, panel ratings, spare circuit breakers and spaces for additional circuit breakers.

8. Submit one copy in final form 15 days prior to final inspection. This copy will be returned after final inspection, with Engineer comments. Revise content of documents as required prior to final submittal.
9. Submit final revised copy within ten days after final inspection.
10. Submit operation and maintenance data in electronic format using USB flash drive storage media.

1.12 REGULATORY REQUIREMENTS

A. When these specifications call for materials or construction of a better quality or larger sizes than required by the following codes and standards, the provisions of the specifications shall take precedence.

B. Provide, without extra charge, any additional materials and labor which may be required for compliance with these codes and standards even though the work is not mentioned in these specifications or shown on the contract drawings.

C. Perform the work of this division in strict accordance with the following authorities. The latest revision of these codes accepted by the authority having jurisdiction as of the date of the contract documents shall apply.

1. The electrical, building, fire, and safety codes of the state and county or city in which the work is being performed.
2. The National Electric Code, NFPA 70 (NEC).
3. The National Fire Protection Association Code (NFPA).
4. International Building Code (IBC).
5. International Energy Conservation, Fire, and Electrical Codes (ICC).

1.13 REFERENCE STANDARDS

A. Perform the work of this division using the standards of the following organizations, as referred to in technical sections, as a minimum requirement for construction and testing. Unless specified otherwise in Bidding and Contract Documents or Division 01, the latest revision current as of the date of the contract documents shall apply.

1. American National Standards Institute (ANSI)
2. American Society for Testing and Materials (ASTM)
3. International Code Council (ICC)
4. Institute of Electrical and Electronics Engineers (IEEE)
5. National Electrical Code (NEC) (NFPA 70)
6. National Electrical Manufacturer's Association (NEMA)
7. National Fire Protection Association (NFPA)
8. The Occupational Safety and Health Act (OSHA)
9. Underwriters Laboratory Inc. (UL)
10. American Association of State Highway and Transportation Officials (AASHTO)
11. American Society of Heating, Refrigerating, and Air Conditioning Engineers (ASHRAE)
12. Maryland Occupational Safety and Health Act (MOSHA)
13. Illuminating Engineering Society of North America (IESNA)

1.14 TEMPORARY STORAGE

A. Maintain upon premises, where directed, a storage area, and be responsible for contents within these areas. Provide security measures necessary for this area.

B. Area shall be maintained and shall be returned to original condition at the completion of the project.

C. Store electrical construction materials such as wire, raceways and boxes, devices, and equipment in buildings, enclosed trailers, or portable enclosed warehouses.

1. Materials and products subject to damage from moisture: Store in dry locations. If necessary, protect with protective wraps or covers.
2. Plastics and other materials and products subject to damage from heat or cold: Store at manufacturer's recommended temperatures.
3. Plastics and other materials and products subject to damage from sunlight: Protect from sunlight.

D. Electrical equipment such as motor controllers, panelboards and circuit breakers stored before installation and installed during construction: Provide clean, dry locations at manufacturer's recommended temperatures, and cover or wrap if required to protect from incidental damage.

1.15 PROTECTION

A. Control dust resulting from construction work to prevent its spread beyond the immediate work area, and to avoid creation of a nuisance.

1. Do not use water to control dust. Use drop cloths or other suitable barriers.

©2023 James Posey Associates, Inc. 7753-22

2. In areas where dirt or dust is produced as a result of the work, sweep daily, or more often as required.
3. Provide walk-off mats at entries and replace them at regular intervals.
4. Construct dust partitions, where indicated on the drawings or as required.
5. Protect areas occupied by Owner's personnel or equipment.

B. Each trade and subcontractor is responsible for preventing damage and soiling of work performed by other trades or subcontractors. Each trade and subcontractor is responsible for providing temporary protection of its own work.

1. Protect work from spills, splatters, drippings, adhesives, bitumens, mortars, paints, plasters, and damage from welding or burning.
2. Protect finished work from damage, defacement, staining, or scratching.
3. Protect finishes from cleaning agents, or grinding and finishing equipment.
4. Protect adjacent and finished work from damage, using tape, masking, covers or coatings and protective enclosures.
5. Coordinate installations and temporarily remove items to avoid damage from finishing work.

C. Repair damage or soiling to the complete satisfaction of the Architect; replace any materials or work damaged to such an extent that they cannot be restored to their original condition, at no addition to the Contract sum.

D. Protect work stored in place and supplies stored in the building.

1. Store materials and products, subject to damage from moisture, in dry locations. If necessary, protect in wraps or covers.
2. Store plastics, other materials, and products subject to damage from heat or cold at manufacturer's recommended temperatures.

E. Protect electrical materials and products from weather events and accidents of construction.

F. Use of sidewalk or roadway areas outside of the property lines shall be with permission and approval of the local authorities having jurisdiction.

1.16 FIRE PROTECTION

A. As a minimum, provide hand-carried, portable, UL-rated extinguishers with each work crew working inside the building.

B. Select extinguishers in accordance with NFPA 10 and NFPA 241 for classification, extinguishing agent, and size required by location and class of fire exposure.

1.17 PROJECT CONDITIONS

A. Drawings showing utilities in concealed locations are based on the best information available but are not represented as being precisely correct. Work of the contract includes digging, cutting, drilling, using nondestructive methods, and other methods of locating concealed utilities in the field, as well as patching and repairing as specified in "Cutting and Patching" below.

B. If, in the course of the work, workers encounter a material they suspect to present some hazard:

1. Promptly notify the Owner in writing.
2. Do not perform any work which would disturb the suspected material until written instructions have been received.

1.18 WARRANTY

A. Work and equipment provided as work of this division shall be fully warranted under the general project warranty. In addition, provide added special warranties as specified in individual sections.

B. During the correction period, the Contractor shall begin correcting any work found to be not in accordance with the requirements of the Contract Documents within 4-hours of receiving written notice from the Owner. Provide detailed schedule for completion of work within 24-hours of receiving written notice from the Owner and revise schedule based on any Owner comments generated. Except as otherwise required in General Conditions and Division 01, the correction period is one year after the date of substantial completion of the work. Work requiring correction shall promptly be repaired or completely replaced at no addition to the Contract Sum.

   1. Service reports for warranty work shall be provided to the Owner.

C. When use of the permanent equipment has been permitted for temporary services during construction of the building, the warranty and correction periods shall nevertheless begin at the time of substantial completion, unless another date of acceptance has been agreed to by the Owner.

D. Special warranties are warranties required by individual specification sections, incidental product warranties, manufacturers' standard warranties, installer or subcontractor service agreements, and other individual warranties in addition to the general project warranty.

E. Provide copies of warranties as required for Operation and Maintenance Manual specified above, and by Division 01.

F. For items of work delayed beyond date of substantial completion, provide updated submittal within ten days after acceptance, listing date of acceptance as start of warranty period.

PART 2 - PRODUCTS

Not used.

PART 3 - EXECUTION

3.1 CUTTING AND PATCHING

A. General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.

B. Cut walls, floors, partitions, roofs, and other appurtenances for the passage or accommodation of conduits. Close superfluous openings and remove debris caused by work of this division.

C. No cutting of any structure or finish shall be done until the condition requiring such cutting has been examined and approved by the Architect.

D. New or existing surfaces disturbed as a result of such cutting or otherwise damaged shall be restored to match original work and materials used for any patching or mending shall conform to the class of materials originally installed.

E. Refinish surfaces to match adjacent finish. For continuous surfaces, refinish to nearest intersection or natural break. For an assembly, refinish entire unit.

3.2 TEMPORARY FACILITIES

A. Temporary water facilities, electricity, telephone, toilet facilities, and temporary heat, shall be provided as specified in Division 01.

3.3 PROGRESS MEETINGS

A. Progress meetings shall be held as specified in Division 01, and also when and if the Contractor or Engineer finds them necessary or advantageous to progress of work.

B. Contractor, those subcontractors and those material suppliers concerned with current progress or with the scheduling of future progress, Architect and Owner shall each be represented at these meetings by persons familiar with the details of work and authorized to conclude matters relating to work progress.

END OF SECTION