SECTION 26 0504

ELECTRICAL DEMOLITION

PART 1 - GENERAL

1.1 SECTION INCLUDES

A. Extent and location of demolition are shown on the drawings.

1.2 RELATED SECTIONS

A. Demolition: Division 01.

1.3 SUBMITTALS

A. Shop drawings: Demolition and removal procedures and schedules.

B. Project record documents: Record drawings.

1.4 QUALITY ASSURANCE

A. Demolition shall be carried out as expeditiously as possible, in accordance with accepted practice and applicable building code provisions.

1.5 PROJECT CONDITIONS

A. If, in the course of the work, workers unexpectedly encounter a material not identified for special removal but which they suspect to be asbestos, to contain lead or PCBs, or to present some other hazard:

1. Promptly notify the Owner and Engineer in writing.
2. Do not perform any work which would disturb the suspected material until written instructions have been received.

B. Protect adjacent materials indicated to remain. Install and maintain dust and noise barriers to keep dirt, dust, and noise from being transmitted to adjacent areas. Remove protection and barriers after demolition operations are complete.

C. Locate, identify, and protect mechanical and electrical services passing through demolition area and serving other areas outside the demolition limits. Maintain services to areas outside demolition limits. When services must be interrupted, install temporary services for affected areas.

PART 2 - PRODUCTS

Not used.

PART 3 - EXECUTION

3.1 PREPARATION

A. Protect existing building and equipment that is to remain, particularly to prevent entry of either dust or water. Ensure weathertightness at all times. Keep materials on hand to patch and maintain protection.

©2023 James Posey Associates, Inc. 7787-23

3.2 DEMOLITION

A. Comply with demolition and disposal requirements of Division 01.

B. Perform removal work neatly with the least possible disturbance to the building.

C. Provide temporary barriers, danger signals, and appurtenances for protection of personnel and equipment during removal operations.

D. Demolish, remove, demount, and disconnect inactive and obsolete conduit, fittings and specialties, equipment, and fixtures.

   1. Conduit and ducts embedded in floors, walls, and ceilings may be abandoned in place if they do not interfere with new installations. Cut back to at least one inch below finished surface.
   2. Remove materials above accessible ceilings.
   3. Disconnect and cap items to remain behind finished surfaces.
   4. Patch and repair surface materials as required in Division 01 and Section 26 0101 article, “Cutting and Patching.”

E. Remove the anchors, bolts, and fasteners associated with conduit and equipment to be removed.

3.3 DISPOSAL

A. Dispose of equipment and materials removed, and rubbish and waste material, as work progresses. Do not allow demolition debris to accumulate on site. Remove products of demolition from the building daily.

END OF SECTION