

**Office of Finance
Division of Procurement
MONTGOMERY COUNTY PUBLIC SCHOOLS
45 W. Gude Drive, Suite 3100
Rockville, Maryland 20850**

May 21, 2024

QUESTIONS AND ANSWERS

**The following are questions and responses regarding
IFB No 9774.1 GENERATOR AND ELECTRICAL EQUIPMENT REPLACEMENT
AT NORTHWEST HIGH SCHOOL**

Question 1	Is NETA testing required for this project? If so, please provide NETA testing specification section referenced in multiple spec sections.
Answer 1	Perform tests in accordance with NETA Acceptance Testing Specification per specification requirements. There are inspection and test procedures in NEMA ATS for circuit breakers, generators, automatic transfer switches, and low-voltage surge arrestors. For panelboards and generator docking station, perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification for molded-case circuit breakers. For surge protective devices, perform each visual and mechanical inspection and electrical test in accordance with NETA Acceptance Testing Specifications in section for Surge Arresters, Low-Voltage, except for inspection and test procedures involving anchorage and bolted connections.